



RIGHT SIDE OF ROAD

IN MEDIAN ISLAND

NOTES:

1. ALL SIGNS SHALL BE INSTALLED ACCORDING TO STANDARD PRACTICE, WITH THE LARGER SIGN MOUNTED HIGHEST ON THE POLE.
2. POST SHALL BE 4"X4" REDWOOD POST SURFACED ON 4 SIDES, SET WITH WOODEN ANCHOR ATTACHED TO POST TO PREVENT ROTATION IN THE HOLE.
3. WHEN A POST FOR SUPPORTING A SIGN IS INSTALLED IN AN AREA OF FLAT CONCRETE, THE POST SHALL BE INSTALLED IN A REMOVABLE 1' SQUARE OF 2" THICK CONCRETE AS SHOWN IN DETAIL.
4. THE FINAL LOCATION OF ALL SIGN AND POLES ARE SUBJECT TO THE APPROVAL OF THE ENGINEER IN THE FIELD.
5. THE BID PRICE FOR SIGNS SHALL INCLUDE INSTALLATION AND ALL HARDWARE REQUIRED FOR INSTALLATION.

▲		
Rev.	Approved	Date

CITY OF CYPRESS
 DEPARTMENT OF PUBLIC WORKS
 ENGINEERING DIVISION

APP. *[Signature]* 12/12/99
 Director of Public Works Date

**SIGN INSTALLATION
 DETAIL**

STD. PLAN NO. **401**